

**ADDENDUM #1**  
**February 2, 2012**

LAFAYETTE CITY-PARISH CONSOLIDATED GOVERNMENT  
LAFAYETTE, LOUISIANA  
BID FOR ST. ESPRIT ROAD BRIDGE REPLACEMENT

TO: ALL VENDORS AND OTHERS TO WHOM SPECIFICATIONS HAVE BEEN ISSUED

THIS ADDENDUM IS HEREBY MADE A PART OF THE CONTRACT DOCUMENTS TO THE SAME EXTENT AS THOUGH IT WERE ORIGINALLY THEREIN:

ITEM #1: Section F – Louisiana Uniform Public Work Bid Form has been revised to include the following revisions: Revised Bid Form must be used to submit bid.

Item 303-01-00100 In-Place Soil Cement 4” Thick; with a quantity of 522 SY  
Has been removed and replaced with:

Item 302-02-01000 Class II Base Course (4” Thick); with a quantity of 522 SY

Item 303-01-00200 In-Place Soil Cement 8.5” Thick; with a quantity of 685 SY  
Has been removed and replaced with:

Item 302-02-02000 Class II Base Course (8 1/2” Thick); with a quantity of 685 SY

An additional pay item: 306-02-00200 Scarifying & Compacting Roadbed (8 1/2” Thick); with a quantity of 590 SY

The quantity for Item 805-02-00200 Structural Concrete Class A(M) 137 CY;  
has been corrected to 78 CY

ITEM #2: An updated Summary of Quantities, Sheet 3 of the Construction Plans, is attached to this Addendum and shows the pay item and quantity revisions listed above.

ITEM #3: The ECO-SPAN precast concrete arch bridge system has been approved for use on this project.

ITEM #4: Standard Plan BM-01 (2 sheets) for Bedding Material Details is attached to this Addendum and is hereby made a part of construction documents.

ITEM #5: A Joint Seal Details sheet related to the precast concrete structure is attached to this Addendum and is hereby made a part of construction documents.

**NOTE: BIDDER SHALL ACKNOWLEDGE RECEIPT OF ALL ADDENDA(S) IN THE SPACE PROVIDED ON THE BID FORM.**